

ADDENDUM #3

To the

BIDDING AND CONTRACT DOCUMENTS

For the

GLENROCK TOWN SQUARE


Project No. 19-021

**Prepared for:
Town of Glenrock
219 South Third Street
Glenrock, WY 82637**

Date of the Addendum: October 13, 2020

Receipt of this Addendum must be acknowledged by filling in the spaces provided below and including one (1) copy attached to the bid.

APPROVED:



Jared Fehninger, Project Manager

ACKNOWLEDGEMENT OF RECEIPT OF
ADDENDUM

Company

Name

Signature

Title

Receipt Date

ADDENDUM #3

To the

BIDDING AND CONTRACT DOCUMENTS

For the

GLENROCK TOWN SQUARE

Project No. 19-021

Date of the Addendum: October 13, 2020

This Addendum No. 3 to the Bidding Information and Construction Specifications and the Drawings is hereby made a part of the Contract Documents, for the above entitled project, to the same extent as though it were originally contained therein.

All bidders are expected to thoroughly examine each item enumerated herein, regardless of its apparent application and shall be responsible for furnishing all labor and materials required in the division of work that the items indicate.

I. GENERAL INFORMATION & CLARIFICATIONS

- A.** The area in front of the stage labeled “FLEX HARDSCAPE” is the typical concrete section
- B.** Sewer and water tap fees will be waived by the Town.
- C.** The splash pad is considered flatwork and shall be constructed according to the Geotechnical report Addendum No. 1.

II. DRAWINGS

- A. Drawing Sheet O-3.0: ADD “OVER NON-WOVEN SEPARATION FABRIC” to volleyball court note.**
- B. Drawing Sheet PG-1.0: CLARIFICATION - Unshaded 2-foot dimensioned section is a concrete wall per detail on PG-1.1 without railings. The wall starts at the sidewalk grade at the south end and maintains that elevation around the corner to the west until it meets up with the shaded wall.**

- C. **Drawing Sheet PG-1.1:** REPLACE note regarding base course with “4-INCHES OF 90% COMPACTED GRADING ‘W’ BASE COURSE OVER TENCATE MIRAFI RS380i GEOSYNTHETIC FABRIC.”
- D. **Drawing Sheet PG-2.0:** REPLACE note: “POURED IN PLACE RUBBER SURFACING, SEE DETAIL” with “AREA TO RECEIVE 4” OF GRADING ‘W’ BASE OVER SEPERATIOIN FABRIC, SUBGRADE TO BE FINISHED PER GEOTECHNICAL REPORT ADDENDUM No.1”
- E. **Drawing Sheet D-2.0:** Detail 4- CONCRETE STAIRCASE; **DELETE** note: “NO. 3 NOSING BAR, BEND DOWN 4” AT ENDS.” There will be no nosing bar required.
- F. **Drawing D-4.0:** **CLARIFICATION** - The seatwalls around the fire pits are constructed per the CONCRETE LAWN STEPS detail
- G. **Drawing D-4.0:**
- i) **DELETE** note “NONWOVEN GEOTEXTILE SEPARATION FABRIC”.
 - ii) **REPLACE** note “ULTRABASESYSTEMS GEOSYNTHETIC STABILIZATION PERMEABLE FABRIC” with “TENCATE MIRAFI RS380i STABILIZATION FABRIC”

END OF ADDENDUM